BRUHATH BANGALORE MAHANAGARA PALIKE

EXECUTIVE ENGINEER, YELAHANKA DIVISION

Name of Work : Construction of Additional floor to Kenchenahalli Samudhaya Bhavana in Ward No-01.

EXTRA ITEM RATE LIST (EIRL)

Sl No	Item Of Work	Unit	Estimate Qty	Rate in Rs. Considering 2022-24 PWD SR	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
Eirl-1	Providing & fixing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete as per design drawings (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as per the direction of Engineer in charge.0.63 mm thick with zinc coating not less than 275 g/ m^2 Pwd Sr 2023-24 Vol-03 Page No 21 Item No 7.1.1)	Sqm	7.04	966.90	6806.98	Additonal Item	No	Savings Amount in the Estimate	Yes, Sr 2023-24 Vol-03 Page No 21 Item No 7.1.1)	
Eirl-2	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including grouting the joint with white cement & matching pigments etc. complete.Size of Tile 500x500 mm (P.No. 61, I.No. 9.17.1 of PWP & IWTD SR 2023-24)	Sqm	4.44	1139.60	5059.82	Additonal Item	No	Savings Amount in the Estimate	Yes, (P.No. 61, I.No. 9.17.1 of PWP & IWTD SR 2023-24)	
Eirl-3	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer- in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m2, including pointing in white cement mixed with pigment of matching shade complete.(P.No. 71, I.No. 10.14 of PWP & IWTD SR 2023-24)	Sqm	20.58	1071.40	22049.41	Additonal Item	No	Savings Amount in the Estimate	Yes, Pwd Sr 2023-24 Vol-03 Page No 21 Item No 7.1.1	

Jo	Item Of Work	Unit	Estimate Qty	Rate in Rs. Considering 2022-24 PWD SR	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
Eirl-4	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid(P.No. 123, I.No. 14.3.1 of PWP & IWTD SR 2022-23)	Each	2.00	5505.50	11011.00	Additonal Item	No	Savings Amount in the Estimate	Yes, P.No. 123, I.No. 14.3.1 of PWP & IWTD SR 2021-22)	
Eirl-5	Providing and fixing wash basin with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required: using White Vitreous China Wash basin size 550x400 mm with a 15 mm CP Brass single hole basin mixer. (P.No. 83, I.No. 12.26 of PWP & IWTD SR 2022-23)	Each	2.00	3958.90	7917.80	Additonal Item	No	Savings Amount in the Estimate	Yes, P.No. 83, I.No. 12.26 of PWP & IWTD SR 2018-19	
	TOTAL EIRL AMOUNT				52845.01					

PERCENTAGE OF EXCESS COMPARING TO SANCTIONED COST $\frac{52845.01}{4362715.00} \times 100 = 1.21\%$

Assistant Engineer
BBMP-Bangalore

Assistant Executive Engineer
BBMP-Bangalore

Asst. Executive Engineer
Yelahanka Sub. Divison
(BBMP Ynk. Zn)
Yelahanka, Bangalore

Executive Engineer
BBMP-Bangalore

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಕಾರ್ಯ ನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ಯಲಹಂಕ ವಿಭಾಗ